



Louisiana Stone  
**Workplace Safety Assessment**  
 Job Hazard Analysis (JHA)



Document Control #:	Stone-JHA-009	Revision Date:	01/17/2024
Document Title:	Job Hazard Analysis (JHA)	Issue #:	1.0
Department:	Warehousing	Frequency:	Annually
Personal Protective Equipment Required:	Safety glasses, safety shoes, safety vest, hard hat, gloves	Completed by:	Name of Company Representative Here

### Removing Material from a Flatbed Trailer

Task Description	Hazard	Control
Securing Trailer	Trailer movement	<ul style="list-style-type: none"> <li>• If drop trailer is to be unloaded, two chocks and trailer jack required</li> <li>• If trailer is live unloaded, two chocks or dock lock are required</li> </ul>
Releasing Tie Down Straps	Strap breakage	<ul style="list-style-type: none"> <li>• Stand clear of straps arc of travel while relieving tension</li> </ul>
	Slabs tipping / falling	<ul style="list-style-type: none"> <li>• Consider weather conditions such as rain or wind. If necessary get more help</li> <li>• Be aware of the "Fall Shadow" and keep at least arm's length away</li> </ul>
Removing Slabs or Bundles from Flatbed	Struck by moving slabs / bundles	<ul style="list-style-type: none"> <li>• As bundles or slabs are freed using slings or cables stay clear of the Fall Shadow to either side of bundles and in front of bundles               <ul style="list-style-type: none"> <li>○ Keep one hand on the bundle and stay one arm length away</li> <li>○ Never try to drag a leaning bundle</li> </ul> </li> </ul>

		<ul style="list-style-type: none"> <li>• Ensure trailer maintains proper balance (if trailer becomes unbalanced then additional precautions must be taken: legs, chains, straps, etc.)</li> </ul>
	Unloading	<ul style="list-style-type: none"> <li>• Remove individual slabs or bundles one at a time</li> <li>• No one is allowed in the vicinity of the work that is not directly engaged to the work process</li> <li>• Always maintain 3 points of contact</li> </ul>
	Cable Breakage	<ul style="list-style-type: none"> <li>• Inspect cables prior to use, replace any questionable cable</li> </ul>

**Rationale or Comment:**

- Know the weights of bundles and slabs and ensure they do not exceed removal equipment’s rated capacity.
- If using a boom crane ensure adequate clearance from overhead wires or other obstacles.
- Be aware of uneven terrain and potential hazards.
- DO NOT try to stop a falling slab. *Get out of the way!*

**End of Document**

**Disclaimer**

*This document is written as a general guideline. MIA+BSI and its Member companies have neither liability nor can they be responsible to any person or entity for any misunderstanding, misuses, or misapplication that would cause loss or damage of any kind, including loss of rights, material, or personal injury, or alleged to be caused directly or indirectly by the information contained in this document.*